	8	7	6		5	
ITEM	PART NO.	DESC	CRIPTION	QTY.	WEIGHT	
1	MTF1543.02	SELF SPLICING COA	X COVER (8 RUN COAX) 1	77.89 LBS	
2	MT-F1599	PVC ROOF SLEEPER	R FOR 8 RUNS OF COAX	3	5.30 LBS	
3	MTF1542HK	HARDWAR	E KIT (ITEMS 4-6)	1		
4	MTF1542.03	ROOF TO	P COVER CLIP	6	0.49 LBS	
5	GB-03125	3/8" X 1-1/4	" GALV BOLT KIT	8	0.11 LBS	
6	GWF-03	3/8" GALV	FLAT WASHER	16	0.02 LBS	

		3	2		1	
			REVISIONS			7
	REV.	ZONE	DESCRIPTION	BY	DATE	
	А		INITIAL RELEASE	JTS	04/27/01	
	В		UPDATE ROOFTOP COVER CLIP, COVER CHANGED TO SELF SPLICING, ADDED SPLICING FASTENERS	ACG	02/02/06	
	С		ADDED HOLE TO ITEM 4	ACG	03/06/06	
~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	> `		0	0	)	D
						C
		5 6				В

-	
В	• • •
	° °
А	

NOTES:

8

D

	property of ANDREW CORPORATION and may be only for the specific purpose authorized in wr	e used	ACG	1 of 1
	Andrew Corporation. ALL DIMENSIONS ARE IN INCHES U.O.S. TOLERANCES UNLESS OTHERWISE SPECIFIED:		CHECKED BY: TP	scale: NTS
	$X = \pm .06$ ANGLES XX = $\pm .03$ FRACTIONS	±2° ±1/32	DATE: 02/02/06	A568
	$XXX = \pm$ .010 REMOVE BURRS AND BREAK EDGES .005	11/02	REVISION:	GALV A123
	DO NOT SCALE THIS PRI	NT	L	WEIGHT 97.53 LBS
Ť	4		3	

 $\Theta$ 

2

4

G

00

6

1. Ø5/16" HOLE INCLUDED IN ITEM 4 FOR OPTIONAL (NOT INCLUDED) 1/4" SELF- DRILLING SCREW.

7

4

	PART NUMBER MT-FI543
	DESCRIPTION: SELF SPLICING ROOF TOP BRIDGE KIT (8 RUN COAX)
	DRAWING TYPE ASSEMBLY DRAWING
	ORLAND PARK, IL. 60462
Τ	0 1